

**TABLE 8**

**Existing and 20 Year Design Hydraulic and Organic Loadings  
Septage and Hauled Sewage  
(Assuming Six Month Treatment Period)**

Septage and Hauled Sewage Parameters	Existing 2004		20 Year Design 2024 m <sup>3</sup> /day
	m <sup>3</sup> /day	%	
Quantity of Septage	171.3	98.5	230.7
Quantity of Hauled Sewage	0.7	0.4	0.9
Quantity of Port-a-Potty Wastewater	1.9	1.1	2.6
TOTAL Quantity of Septage, Hauled Sewage and Port-a-Potty Wastewater (m <sup>3</sup> /day)	173.9	100	234.2
TOTAL BOD <sub>5</sub> Loading (kg/day)	1217	--	1639
TOTAL TKN Loading (kg/day)	121.7	--	163.9